
# A new Port Facility at Waitangi







#### **Context**

#### **Chatham Islands key facts**

- Chatham Islands are a group of 10 islands situated 800km east of Christchurch.
- Waitangi and Pitt Island are the only habited islands in the group. Remaining Islands are conservation reserves.
- Resident population of 600 people at 2013 census.

#### Ownership and governance of the Chatham Islands infrastructure

- Chatham Islands Council owns Owenga Wharf, water supply, sewerage and solid and hazardous waste management
- Chatham Islands Enterprise Trust owns Pitt and Waitangi Wharves, Airport, Electricity supply and fishing quota.

#### Chatham Islands is a primary sector based economy

- Fishing, agriculture and tourism
  - \$45.7 million in GDP
  - \$69 million exports
  - 360 people employed





# **History**

#### **History of Waitangi Wharf**

- It is the main container, fuel and cargo wharf for the Islands.
- Provides key sea access in an emergency. It's the only wharf capable of handling substantial shipping for transporting freight and livestock.
- Two shipping companies provide freight services to the Island.

#### The wharf specifications

- The wharf was constructed in 1979 by the Ministry of Works and extended in 1993.
- The wharf facilities are 'T' shaped and consists of a concrete Tee Head and Tee stem, and reclamation area for cargo handling and buildings.
- One berth for general cargo, one for stock loading and a berth for smaller fishing vessels.

#### Signs of deterioration

- Long history of deterioration from chloride contamination from the corrosive environment around the Islands.
- The Trust commissioned a feasibility study to determine replacement or repair of the wharf in 2011.
- DIA commissioned structural assessment in 2014, report considered wharf needed to be repaired or replaced within five years.





# **History and Context**







# Why the partnership

#### Government consideration on the redevelopment of Waitangi Wharf

#### Cabinet considered the issues associated with the wharf in August 2014:

 recognised that structural failure to the wharf raised a range of major concerns e.g. health and safety.

#### In light of the risks and to mitigate them Cabinet:

- was prepared to fund structural remedial work to the existing wharf to keep it safe and operational until a replacement wharf is completed;
- approval of funds to undertake preparatory works in order to refine the cost of the rebuild, reduce risk, and reduce possible delays in consenting and construction; and
- saw merit in government agencies collaborating together on the delivery of the wharf redevelopment project.





#### **Procurement**



- Better Public Services Programme Joined up approach to delivery that focuses on VfM encourages innovation.
- Need to bring skilled team on board to produce a robust budget bid for March 2015
- Government Rules of Sourcing allow direct appointment but do not negate the need for
  - Procurement Strategy
  - Supplier evaluation
  - Value for Money test
  - Due Diligence
- MPA on board with skills required
- Alliance Model allows staged engagement with quality and value gates





## **Governance and Decision Making**

- Joint agency Governance underpinned by Transport Agency processes and decision making structure
- DI/NZTA MOU
- NZTA contractual client
- Key stakeholders, CIET, CIP and CCC all observers at governance board





# **Transport**

- Barge (getting stuff to the island), only one barge company with capability in NZ
- Amount of material required from mainland – e.g. precast, roading surface chip is imported for instance currently
- Unloading/loading at Waitangi offer of naval vessels not sufficient to deal with plant and equipment required







#### Accommodation

- Number of beds needed and island capacity current population 500+, number of construction and design people possibly 10% at peak
- If purchasing accommodation, on selling issues very limited market









#### Concrete

- Aggregates/water on island supply
- Quality control of concrete
- Casting on island













# Quarry

- Size of rock original estimate for breakwater was 12-15 tonne rocks barely available in mainland let alone on island
- Volume of material highly variable depths and quality of material
- Hardness of rock (durability)
- Overburden to be moved and site rehabilitation












#### Weather

- Storms and large waves
- Rainfall effecting roads
- Damage to infrastructure/temporary works
- Down time islands cut off for weeks at a time currently

# Days Lost Breakwater length vs cost vs wave height




Note: Graph above is a work in progress as further information and assessments are carried out





#### **Preferred Solution**

#### Plan



- NZTA engaged MPA to develop scheme
- Concept plan and cost estimate by March 2015





# **Preferred Solution**

# **Blocks**














#### **Preferred Solution**

# Dredging







#### **Next Steps**

- Budget Decision May 21st
- Lodge resource consents
- Agree Target outturn Cost
- Award Construction Phase (includes detailed design)
- And then the fund begins
  - Construction start summer 15/16
  - Completion Autumn 2017





# **Questions**







# Thank you



