



## SiD Practice Forum – May 2017

Waterview Tunnel through the eyes of SID

Peter Norfolk – Civil Design Manager for the Well-Connected Alliance









### **Waterview Connection**

COMPLETING THE WESTERN RING ROUTE

# WELL-CONNECTED ALLIANCE PROUDLY DELIVERING



Roads of national significance





## Safety In Design Key Principles

- Use a Risk Management Approach
- Consider the Lifecycle
- **B** Knowledge and Capability
- Consultation, Cooperation and Coordination
- 5 Information Transfer





## **Project Overview**

- 5km long 3-lane motorway comprising 35 lane-km
- Two 2.4 km long 13.1 m (ID) diameter bored tunnels
- Two vent buildings
- Six road bridges 1,700 m total length
- Two long span footbridges and several smaller structures
- Over 3 km of retention structures
- Extensive urban improvements and landscaping
- 5+ years construction period
- Operations and Maintenance responsibilities for 10 years
- \$1.4 billion capital cost






### **Alliance**

- Co-located, collaborative working arrangement actively encouraged and built into project culture
  - Designers
  - Constructors
  - **O&M**
  - Client







## 3-stage design process


Stage 1
Concept Design



Stage 2
Detailed Design



Stage 3
IFC







#### Table 1 Safety in Design Rating Matrix

## SiD on Waterview

Documented Process – part of the Design Management Plar




Table 2: Hierarchy of Control – Hazard Management (Health & Safety)

	1	Elimination	Elimination – Remove the cause or source of hazard     Redesign or Substitute the cause or source with less hazardous one
Use a Risk Management Approach  Consider the Lifecycle  Knowledge and Capability	2	Isolation	<ul> <li>Isolation - isolating the hazard from a person by safe guarding or by space or time separation</li> <li>Engineering Controls – allow for hazard to be designed out and control measures designed in (Drawings and Specifications, Construction Method Statements)</li> </ul>
Consultation, Cooperation and Coordination  Information Transfer	3	Minimisation	<ul> <li>Administrative Controls (JSEA, ITP, Legislative Controls, Supervision and Operations and Management)</li> <li>Training and Induction</li> <li>PPE (Personal Protective Equipment)</li> </ul>



## Workshop / Mini-Group Reviews

- Designers
- Constructors
- O&M Personnel
- Risk Manager








## **Register & Reports**

**Information Transfer** 



	Verification at completion of Stage 2: (name/signature/date)						WELL-CONNECTED				
	Design Manager: Peter Norfolk								ALLIANCE		
	Construction Manager:	Stefa	an Hanke					tion of Transfer by Package Manager:			
	Owner Verifier:	Owner Verifier: Tom Ireland				Date:					
	Recommendat	tion (Stage 1	1)	Resolution: What was done? (5			& 2)		Full/Partial Transfer		
	Recommended Action	Control Category	Action Owner	Stage 1: Incl, Pending or None Stage 2: Completed action	Mitigation Measure	%	Impact	Residual	Phase	New Risk Owner	
i	Para del Composition del Compo	N. Albert Committee	B	to a file of a Library South	The second control to				A	P. 100 B. A. 11111	



## **Briefings**

- Design handover briefings design team to construction team at completion of design
- Construction Execution Plan briefings design team, Construction team, QA team







## SiD Examples

Lane Control for the tunnels









## **SiD Examples**

Motorway Drainage





**SiD Examples** 





